#### ICT6: LaRC DAAC - SDPF Interface Confidence Test

#### Background:

The Science Data Processing Facility at GSFC has the responsibilities for receiving the raw spacecraft telemetry data, performing the necessary level zero processing and transferring the L0 data products to the appropriate users for further processing. For the EOSDIS project, SDPF receives CERES L0 data and forwards both 24 hour products and quicklook products to the LaRC DAAC after completion of L0 processing. In addition, the SDPF also transfers TRMM Ephemeris (Predictive/Definitive Ephemeris) Data Products to the LaRC DAAC.

The communicating subsystems for data transfer between the SDPF and the LaRC DAAC are the Data Distribution Facility (DDF) Electronic Distribution System (EDS) and the Ingest Subsystem, respectively. With EBnet providing the communications path between them. The message flows supporting these product transfers are presented in Table ICT6-1. The Sensor Data Processing Facility (SDPF) Consumer Products and Interface Specification Document (510-203.102) provides detailed descriptions for each message type. Exhibit ICT6-1 presents the sequencing of these messages between the SDPF DDF EDS and the LaRC DAAC.

#### **Test Objectives:**

- To verify that CERES Level 0 and Quick Look Data sets and ephemeris data (orbit and attitude data files) can be transferred from the SDPF to the LaRC DAAC.
- To verify proper implementation of interface error handling and exception processing.

Note: The SDPF control messages are handled by the Management Server Element (MSE) and the actual data files are handled through the File Server Element (FSE)

| From      | То        | Data Flow                              | Communications<br>Link |
|-----------|-----------|--|------------------------|
| DDF MSE   | LaRC DAAC | Authentication Request                 | EBnet                  |
| LaRC DAAC | DDF MSE   | Authentication Response                | EBnet                  |
| DDF MSE   | LaRC DAAC | Data Availability Notice (DAN)         | EBnet                  |
| LaRC DAAC | DDF MSE   | Data Availability Acknowledgment (DAA) | EBnet                  |
| DDF FSE   | LaRC DAAC | CERES L0 Data Files                    | EBnet                  |
| DDF FSE   | LaRC DAAC | CERES Quick-look Data Files            | EBnet                  |
| DDF FSE   | LaRC DAAC | TRMM Ephemeris Data Files              | EBnet                  |
| LaRC DAAC | DDF MSE   | Data Delivery Notice (DDN)             | EBnet                  |
| DDF MSE   | LaRC DAAC | Data Delivery Acknowledgment (DDA)     | EBnet                  |

**Table ICT6-1 Message Flows** 

#### Requirements Verified:

TRMM1010\* TRMM1040 TRMM1050 TRMM1060 TRMM1070 TRMM1080 TRMM1090\*\*TRMM1130 TRMM1180 TRMM1195 TRMM1200 TRMM1210 TRMM1280 TRMM8100


\*transfer only \*\* notification only

## **Test Configuration:**

Hardware and software configurations at each ECS site are managed and tracked by the M&O organization at that site. The most current configuration status report will be obtained prior to the start of testing and be referenced in the test report. EXHIBIT ICT6-2 presents the current hardware configurations.

# **TBS**

**EXHIBIT ICT6-2 SDPF - LaRC Configuration** 



**Exhibit ICT6-1 SDPF to LaRC Message Flow** 

#### Participants and Support Requirements:

Participants:

SDPF (DDF) Operations personnel

LaRC DAAC M&O personnel

**I&T TC** 

Communications:

Voice: SDPF - LaRC DAAC (Circuit **TBD**)

Data: SDPF connects to EBnet for transfer to LaRC DAAC

IP Addresses: TBS

Equipment and Hardware:

Hardware:

Software:

Test Tools: **TBD** - Potentially DDF Simulator (DESIM) - Since the ability to produce errors has not been built into the DDF design, the need for DESIM maybe necessary in order to test the ability of the ECS to detect certain error conditions. Other error checking conditions can be performed through manipulation of LaRC DAAC acceptable parameters (which should be available as flat files or database tables).

#### Test data:

| Description/ Characteristics                        | Source           | File/Script Name - Physical loc.             |
|---|------------------|--|
| CERES L0 Product - Nominal Product - 24 hour        | CERES Instrument | File/Script Name - TBD                       |
| day group (simulated)                               | Team or SDPF     | Physical Location - Data Files spread over 2 |
|   |                  | or more SDPF DDF File Servers (FSE)          |
| CERES Quick-Look Product - Nominal Product          | CERES Instrument | File/Script Name - TBD                       |
| - Data from one Spacecraft Contact Session          | Team or SDPF     | Physical Location - Data Files spread over 2 |
| (simulated)   |                  | or more SDPF DDF File Servers (FSE)          |
| Series of multiple CERES Products (L0 and           | CERES Instrument | File/Script Name - TBD                       |
| Quick-Look) to be placed into the DDF               | Team or SDPF     | Physical Location - Data Files spread over   |
| distribution queue in quick succession ?????        |                  | 2 or more SDPF DDF File Servers (FSE)        |
| Data/files with error conditions for ICT 6. 5 tests |                  |  |
| TBD   |                  |  |
|   |                  |  |
| TRMM Ephemeris Data                                 | FDF              | File/Script Name - TBD                       |
| - Prelaunch Ephemeris Data                          |                  | Physical Location - Data Files spread over 2 |
| - Definitive Ephemeris Data                         |                  | or more SDPF DDF File Servers (FSE)          |
| - Predictive Ephemeris Data                         |                  |  |

SDPF products consist of multiple Data files and their associated SFDU Headers. Reference the SDPF - Consumer Systems ICD for the detailed format descriptions of SDPF products.

## **Test Case Descriptions:**

#### V1-ICT-06-001 CERES L0 Product Transfers

Test case description: CERES LO Product Transfers

This testcase will verify the ability of the LaRC DAAC to receive CERES L0 Data Products from the SDPF. The test begins with the system operators verifying the operational readiness of their respective systems. The SDPF operator will then perform the necessary steps to make a CERES L0 Data Product enter the distribution queue. The automated data transfer will be monitored at both the SDPF and LaRC DAAC locations, to verify the proper sequencing of control messages and the transfer of the data product. Upon completion of the automated transfer, the LaRC DAAC L0 will store the data files and verify that the transfer is satisfactory.

#### Mapped Requirements:

| TRMM1010#A | TRMM1040#A | TRMM1050#A | TRMM1060#A |
|------------|------------|------------|------------|
| TRMM1070#A | TRMM1080#A | TRMM1180#A | TRMM1280#A |
| TRMM8100#A |            |            |            |

Prerequisite conditions

#### Test inputs

CERES L0 Data product

#### Expected test results

Transfer of DAN, DAA, DDN, DDA, between SDPF and LaRC and transfer of CERES LO Data Product to LaRC

#### Methods for analysis

Verify successful. transfer of DAN, DAA, DDN, DDA, between SDPF and LaRC and transfer of CERES L0 Data Product to LaRC

#### Assumptions and constraints

#### Test Procedures

| Test<br>Case ID   | Step<br>Type | Station                     | Operator action   | Expected Result  | Comments  | Allocated<br>Require<br>ments |
|-------------------|--------------|-----------------------------|---|--|---|-------------------------------|
| V1-ICT-<br>06-001 | 1.001        | SDPF                        | Verify SDPF is operational in<br>appropriate Mode and<br>Configuration - i.e. Capable<br>of supporting Electronic<br>Distribution | SDPF is operational and capable of supporting Electronic distribution.   | If it is not in<br>proper mode, the<br>system shall be<br>appropriately<br>initialized.                     | 3-3-3-3                       |
| V1-ICT-<br>06-001 | 1.002        | LaRC<br>DAAC                | Verify LaRC DAAC is operational in a mode capable of supporting test.   | LaRC DAAC is operational in a mode capable of supporting test.   | If it is not in<br>proper mode, the<br>system shall be<br>appropriately<br>initialized.                     |                               |
| V1-ICT-<br>06-001 | 1.003        | SDPF<br>and<br>LaRC<br>DAAC | Validate IP Address and<br>Password information   | Both systems should contain the valid information.   |   |                               |
| V1-ICT-<br>06-001 | 1.004        | SDPF                        | Verify connection capabilities between DDF MSE and DAAC   | Successful 'Ping' of other system  | This is the interface for transfer of control messages  |                               |
| V1-ICT-<br>06-001 | 1.005        | LaRC<br>DAAC                | Verify connection capabilities<br>between DAAC and DDF<br>FSE   | Successful 'Ping' of other<br>system   | This is the interface for Product Transfer  |                               |
| V1-ICT-<br>06-001 | 1.006        | SDPF                        | Verify contents of test data  | The test data shall be CERES L0 data and is in the format as required by the test.   | Generically, this step is to verify the data to be transmitted during the test execution is in fact "good". | TRMM10<br>40#A                |
| V1-ICT-<br>06-001 | 2.001        | SDPF                        | Initiate procedures for the automated transfer of CERES L0 Data Product.  | The SDPF will transmit the 'Authentication Request' to the LaRC DAAC.  |   |                               |
| V1-ICT-<br>06-001 | 2.002        | LaRC<br>DAAC                | Verify receipt and validation<br>of 'Authentication Request',<br>verify 'Authentication<br>Response' is sent to SDPF.             | LaRC DAAC shall accept and validate the 'Authentication Request' and respond with a valid 'Authentication Response'  |   |                               |
| V1-ICT-<br>06-001 | 2.003        | SDPF                        | Verify receipt and validation<br>of 'Authentication Response'<br>and issue of a DAN   | The Network connection<br>between the SDPF and LaRC<br>DAAC shall be successfully<br>opened and a DAN is issued by<br>SDPF   |   |                               |
| V1-ICT-<br>06-001 | 2.004        | LaRC<br>DAAC                | Verify successful receipt and validation of the DAN.  | A message or log file should indicate the successful receipt and validation of the DAN. The data files shall be placed in the Ingest queue and a Short DAA shall be transferred to the SDPF. |   |                               |
| V1-ICT-<br>06-001 | 2.005        | SDPF                        | Verify DAN is transferred to the LaRC DAAC.   | A message or log file should indicate transfer of the DAN.   |   | TRMM10<br>50#A                |
| V1-ICT-<br>06-001 | 2.006        | LaRC<br>DAAC                | Verify successful receipt and validation of the DAN.  | A message or log file should indicate the successful receipt and validation of the DAN. Short DAA shall be transferred to the SDPF.  |   |                               |

| Step<br>Type | Station                                   | Operator action   | Expected Result   | Comments  | Allocated<br>Require<br>ments   |
|--------------|---|---|---|---|---|
| 2.007        | SDPF                                      | Verify the successful receipt of the DAA.   | A message or log file should indicate successful receipt of the DAA   |   |   |
| 2.008        | LaRC<br>DAAC                              | Establish FTP connection with SDPF and issue a "GET" command.   | Establish FTP link with SDPF and Reception of Data  | The files shall be individually FTP'd from the DDF FSE via FTP GET command  | TRMM10<br>60#A  |
| 2.009        | LaRC<br>DAAC                              | Exit FTP connection   | Terminate FTP link with SDPF  |   |   |
| 2.010        | LaRC<br>DAAC                              | Verify that the appropriate files (as indicated in DAN) containing CERES L0 Data are ingested into the ECS and that they are valid. | Upon successful ingest, the data files shall be stored. and are valid   |   | TRMM10<br>10#A,<br>TRMM10<br>70#A,<br>TRMM10<br>80#A<br>TRMM11<br>80#A<br>TRMM12<br>80#A<br>TRMM81<br>00#A  |
| 2.011        | LaRC<br>DAAC                              | Verify that a DDN is sent to<br>the SDPF indicating the<br>successful status of the data<br>transfer.                               | A message or log file should indicate transfer of the DDN.  |   |   |
| 2.012        | SDPF                                      | Verify the successful receipt of the DDN and the transfer of the DDA to the LaRC DAAC.  | A message or log file should indicate successful receipt of the DDN and transfer of the DDA   |   |   |
| 2.013        | LaRC<br>DAAC                              | Verify the successful receipt of the DDA.   | A message or log file should indicate successful receipt of the DDA.  | This step<br>completes the<br>transfer of the<br>CERES LO<br>Product.   | TRMM10<br>10#A  |
| 2.014        | Both                                      | Verify the connection<br>between the two systems has<br>been terminated.  | No connection should exist following the end of the exchange messages.  |   |   |
| 2.015        | LaRC<br>DAAC                              | Query the DAACs archive to verify the storage of the data product and it's associated metadata.                                     | Both the metadata and product should be stored in its appropriate locations.  |   |   |
|              | 2.007 2.008 2.009 2.010 2.011 2.012 2.013 | 2.007   SDPF  | 2.007 SDPF Verify the successful receipt of the DAA.  2.008 LaRC DAAC Exit FTP connection with SDPF and issue a "GET" command.  2.009 LaRC DAAC Exit FTP connection  2.010 LaRC DAAC Verify that the appropriate files (as indicated in DAN) containing CERES L0 Data are ingested into the ECS and that they are valid.  2.011 LaRC DAAC Verify that a DDN is sent to the SDPF indicating the successful status of the data transfer.  2.012 SDPF Verify the successful receipt of the DDN and the transfer of the DDA to the LaRC DAAC.  2.013 LaRC DAAC Verify the successful receipt of the DDA.  2.014 Both Verify the connection between the two systems has been terminated.  2.015 LaRC Query the DAACs archive to verify the storage of the data product and it's associated | 2.007   SDPF   Verify the successful receipt of the DAA.     2.008   LaRC DAAC   Establish FTP connection with SDPF and issue a "GET" command.     2.009   LaRC DAAC   Exit FTP connection with SDPF and issue a "GET" command.     2.010   LaRC DAAC   Exit FTP connection   Terminate FTP link with SDPF and Reception of Data     2.011   LaRC DAAC   Verify that the appropriate files (as indicated in DAN) containing CERS L0 Data are ingested into the ECS and that they are valid.     2.012   SDPF   Verify that a DDN is sent to the SDPF indicating the successful status of the data transfer.     2.013   LaRC DAAC   Verify the successful receipt of the DDA to the LaRC DAAC.     2.014   Both   Verify the successful receipt of the DDA.     2.015   LaRC DAAC   Verify the connection between the two systems has been terminated.     2.016   LaRC DAAC   Query the DAACs archive to verify the storage of the data appropriate locations.     3.000   SDPF   SDPF   SUCCESSFUL Teceipt of the DDA.     4.000   SDPF   SDPF   SDPF   SUCCESSFUL Teceipt of the DDA     5.000   SDPF   SDPF   SUCCESSFUL Teceipt of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the DDA     5.000   SDPF   SUCCESSFUL TECEIPT of the DDA   SUCCESSFUL TECEIPT of the | Type   2.007   SDPF   Verify the successful receipt of the DAA.   A message or log file should indicate successful receipt of the DAA   Establish FTP connection with SDPF and issue a "GET" command.   The files shall be individually FTP'd from the DDF FSE via FTP GET command. |

## V1-ICT-06-002 CERES Quick-look Product Transfers

Test case description: CERES Quick-look Product Transfers

This testcase will verify the ability of the LaRC DAAC to receive CERES L0Quicklook Data Products from the SDPF. The test begins with the system operators verifying the operational readiness of their respective systems. The SDPF operator will then perform the necessary steps to make a CERES L0 Quicklook Data Product enter the distribution queue. The automated data transfer will be monitored at both the SDPF and LaRC

DAAC locations, to verify the proper sequencing of control messages and the transfer of the data product. Upon completion of the automated transfer, the LaRC DAAC will store the data files and verify that the transfer is satisfactory.

#### Mapped Requirements:

| TRMM1010#A | TRMM1040#A | TRMM1050#A | TRMM1060#A |
|------------|------------|------------|------------|
| TRMM1070#A | TRMM1080#A | TRMM1130#A | TRMM1180#A |
| TRMM1280#A | TRMM8100#A |            |            |

## Prerequisite conditions

#### Test inputs

CERES Quick-look Data product

#### Expected test results

Transfer of DAN, DAA, DDN, DDA, between SDPF and LaRC and transfer of CERES Quick look Data Product to LaRC

#### Methods for analysis

Verify successful. transfer of DAN, DAA, DDN, DDA, between SDPF and LaRC and transfer of CERES Quick-look Data Product to LaRC

# Assumptions and constraints

| Test<br>Case ID   | Step<br>Type | Station                     | Operator action   | Expected Result  | Comments  | Allocated<br>Require<br>ments |
|-------------------|--------------|-----------------------------|---|--|---|-------------------------------|
| V1-ICT-<br>06-002 | 1.001        | SDPF                        | Verify SDPF is operational in appropriate Mode and Configuration - i.e. Capable of supporting Electronic Distribution | SDPF is operational and capable of supporting Electronic distribution. | If it is not in proper mode, the system shall be appropriately initialized.             |                               |
| V1-ICT-<br>06-002 | 1.002        | LaRC<br>DAAC                | Verify LaRC DAAC is operational in a mode capable of supporting test.   | LaRC DAAC is operational in a mode capable of supporting test.         | If it is not in proper<br>mode, the system<br>shall be<br>appropriately<br>initialized. |                               |
| V1-ICT-<br>06-002 | 1.003        | SDPF<br>and<br>LaRC<br>DAAC | Validate IP Address and<br>Password information   | Both systems should contain the valid information.                     |   |                               |

| Test<br>Case ID   | Step<br>Type | Station      | Operator action   | Expected Result  | Comments  | Allocated<br>Require                         |
|-------------------|--------------|--------------|---|--|---|--|
| V1-ICT-<br>06-002 | 1.004        | SDPF         | Verify connection capabilities between DDF MSE and DAAC   | Successful 'Ping' of other<br>system   | This is the interface<br>for transfer of<br>control messages  | ments  |
| V1-ICT-<br>06-002 | 1.005        | LaRC<br>DAAC | Verify connection capabilities between DAAC and DDF FSE   | Successful 'Ping' of other system  | This is the interface for Product Transfer  |  |
| V1-ICT-<br>06-002 | 1.006        | SDPF         | Verify contents of test data  | The test data shall be CERES Quick-look data and is in the format as required by the test.   | Generically, this step is to verify the data to be transmitted during the test execution is in fact "good". | TRMM10<br>40#A                               |
| V1-ICT-<br>06-002 | 2.001        | SDPF         | Initiate procedures for the automated transfer of CERES Quick-look Data Product.  | The SDPF will transmit the 'Authentication Request' to the LaRC DAAC.  |   |  |
| V1-ICT-<br>06-002 | 2.002        | LaRC<br>DAAC | Verify receipt and validation<br>of 'Authentication Request',<br>verify 'Authentication<br>Response' is sent to SDPF.               | LaRC DAAC shall accept and validate the 'Authentication Request' and respond with a valid 'Authentication Response'  |   |  |
| V1-ICT-<br>06-002 | 2.003        | SDPF         | Verify receipt and validation of 'Authentication Response' and issue of a DAN   | The Network connection<br>between the SDPF and LaRC<br>DAAC shall be successfully<br>opened. and a DAN is issued<br>by SDPF  |   |  |
| V1-ICT-<br>06-002 | 2.004        | LaRC<br>DAAC | Verify successful receipt and validation of the DAN.  | A message or log file should indicate the successful receipt and validation of the DAN. The data files shall be placed in the Ingest queue and a Short DAA shall be transferred to the SDPF. |   |  |
| V1-ICT-<br>06-002 | 2.005        | SDPF         | Verify DAN is transferred to the LaRC DAAC.   | A message or log file should indicate transfer of the DAN.   |   | TRMM10<br>50#A                               |
| V1-ICT-<br>06-002 | 2.006        | LaRC<br>DAAC | Verify successful receipt and validation of the DAN.  | A message or log file should indicate the successful receipt and validation of the DAN. Short DAA shall be transferred to the SDPF.  |   |  |
| V1-ICT-<br>06-002 | 2.007        | SDPF         | Verify the successful receipt of the DAA.   | A message or log file should indicate successful receipt of the DAA  |   |  |
| V1-ICT-<br>06-002 | 2.008        | LaRC<br>DAAC | Establish FTP connection with SDPF and issue a "GET" command.   | Establish FTP link with SDPF and Reception of Data   | The files shall be individually FTP'd from the DDF FSE via FTP GET command                                  | TRMM10<br>60#A                               |
| V1-ICT-<br>06-002 | 2.009        | LaRC<br>DAAC | Exit FTP connection   | Terminate FTP link with SDPF   |   |  |
| V1-ICT-<br>06-002 | 2.010        | LaRC<br>DAAC | Verify that the appropriate files (as indicated in DAN) containing CERES Quicklook Data are ingested into the ECS and that they are | Upon successful ingest, the data files shall be stored and are valid   |   | TRMM10<br>10#A,<br>TRMM10<br>70#A,<br>TRMM10 |

| Test<br>Case ID   | Step<br>Type | Station      | Operator action   | Expected Result   | Comments  | Allocated<br>Require<br>ments                              |
|-------------------|--------------|--------------|---|---|---|--|
|                   |              |              | valid.  |   |   | 80#A<br>TRMM11<br>80#A<br>TRMM12<br>80#A<br>TRMM81<br>00#A |
| V1-ICT-<br>06-002 | 2.011        | LaRC<br>DAAC | Verify that a DDN is sent to<br>the SDPF indicating the<br>successful status of the data<br>transfer. | A message or log file should indicate transfer of the DDN.                                  |   |  |
| V1-ICT-<br>06-002 | 2.012        | SDPF         | Verify the successful receipt<br>of the DDN and the transfer<br>of the DDA to the LaRC<br>DAAC.       | A message or log file should indicate successful receipt of the DDN and transfer of the DDA |   |  |
| V1-ICT-<br>06-002 | 2.013        | LaRC<br>DAAC | Verify the successful receipt of the DDA.   | A message or log file should indicate successful receipt of the DDA.                        | This step completes<br>the transfer of the<br>CERES Quick-look<br>data Product. | TRMM10<br>10#A<br>TRMM11<br>30#A                           |
| V1-ICT-<br>06-002 | 2.014        | Both         | Verify the connection<br>between the two systems has<br>been terminated.                              | No connection should exist following the end of the exchange messages.                      |   |  |
| V1-ICT-<br>06-002 | 2.015        | LaRC<br>DAAC | Query the DAACs archive to verify the storage of the data product and it's associated metadata.       | Both the metadata and product should be stored in its appropriate locations.                |   |  |

## 6.2 TRMM Ephemeris Data Product Transfers

Test case description:

This testcase will verify the ability of the LaRC DAAC to receive TRMM Ephemeris Data Products from the SDPF. The test begins with the system operators verifying the operational readiness of their respective systems. The SDPF operator will then perform the necessary steps to make a TRMM Ephemeris Data Product enter the distribution queue. The automated data transfer will be monitored at both the SDPF and LaRC DAAC locations to verify the proper sequencing of control messages and the transfer of the data product. Upon completion of the automated transfer, the LaRC DAAC will store the data files and verify that the transfer is satisfactory.

Mapped Requirements

TRMM1195#A TRMM1200#A TRMM1205#A

Prerequisite conditions

# Test inputs

TRMM Ephemeris Data product

# Expected test results

Transfer of DAN, DAA, DDN, DDA, between SDPF and LaRC and transfer of CERES Quick look Data Product to LaRC

## Methods for analysis

Verify successful. transfer of DAN, DAA, DDN, DDA, between SDPF and LaRC and transfer of CERES Quick-look Data Product to LaRC

# Assumptions and constraints

| Test<br>Case ID   | Step<br>Type | Station                     | Operator action   | Expected Result  | Comments  | Allocated<br>Require<br>ments |
|-------------------|--------------|-----------------------------|---|--|---|-------------------------------|
| V1-ICT-<br>06-003 | 1.001        | SDPF                        | Verify SDPF is operational<br>in appropriate Mode and<br>Configuration - i.e. Capable<br>of supporting Electronic<br>Distribution | SDPF is operational and capable of supporting Electronic distribution.                   | If it is not in proper mode, the system shall be appropriately initialized.                                 |                               |
| V1-ICT-<br>06-003 | 1.002        | LaRC<br>DAAC                | Verify LaRC DAAC is operational in a mode capable of supporting test.   | LaRC DAAC is operational in a mode capable of supporting test.                           | If it is not in proper mode, the system shall be appropriately initialized.                                 |                               |
| V1-ICT-<br>06-003 | 1.003        | SDPF<br>and<br>LaRC<br>DAAC | Validate IP Address and<br>Password information   | Both systems should contain the valid information.                                       |   |                               |
| V1-ICT-<br>06-003 | 1.004        | SDPF                        | Verify connection capabilities between DDF MSE and DAAC   | Successful 'Ping' of other system  | This is the interface<br>for transfer of<br>control messages  |                               |
| V1-ICT-<br>06-003 | 1.005        | LaRC<br>DAAC                | Verify connection<br>capabilities between DAAC<br>and DDF FSE   | Successful 'Ping' of other system  | This is the interface<br>for Product Transfer   |                               |
| V1-ICT-<br>06-003 | 1.006        | SDPF                        | Verify contents of test data  | The test data shall be TRMM Ephemeris data and is in the format as required by the test. | Generically, this step is to verify the data to be transmitted during the test execution is in fact "good". |                               |
| V1-ICT-<br>06-003 | 2.001        | SDPF                        | Initiate procedures for the automated transfer of TRMM Ephemeris Data   | The SDPF will transmit the 'Authentication Request' to the LaRC DAAC.                    |   |                               |

| Test<br>Case ID   | Step<br>Type | Station      | Operator action   | Expected Result   | Comments  | Allocated<br>Require<br>ments    |
|-------------------|--------------|--------------|---|---|---|----------------------------------|
|                   |              |              | Product.  |   |   | ments                            |
| V1-ICT-<br>06-003 | 2.002        | LaRC<br>DAAC | Verify receipt and validation<br>of 'Authentication Request',<br>verify 'Authentication<br>Response' is sent to SDPF.                     | LaRC DAAC shall accept and validate the 'Authentication Request' and respond with a valid 'Authentication Response'                   |   |                                  |
| V1-ICT-<br>06-003 | 2.003        | SDPF         | Verify receipt and validation<br>of 'Authentication<br>Response' and issue of a<br>DAN  | The Network connection<br>between the SDPF and LaRC<br>DAAC shall be successfully<br>opened and a DAN is issued by<br>SDPF            |   | TRMM11<br>95#A                   |
| V1-ICT-<br>06-003 | 2.004        | LaRC<br>DAAC | Verify successful receipt and validation of the DAN.  | A message or log file should indicate the successful receipt and validation of the DAN. A Short DAA shall be transferred to the SDPF. |   |                                  |
| V1-ICT-<br>06-003 | 2.005        | SDPF         | Verify DAN is transferred to the LaRC DAAC.   | A message or log file should indicate transfer of the DAN.  |   |                                  |
| V1-ICT-<br>06-003 | 2.006        | LaRC<br>DAAC | Verify successful receipt and validation of the DAN.  | A message or log file should indicate the successful receipt and validation of the DAN. Short DAA shall be transferred to the SDPF.   |   |                                  |
| V1-ICT-<br>06-003 | 2.007        | SDPF         | Verify the successful receipt of the DAA.   | A message or log file should indicate successful receipt of the DAA   |   |                                  |
| V1-ICT-<br>06-003 | 2.008        | LaRC<br>DAAC | Establish FTP connection with SDPF and issue a "GET" command.   | Establish FTP link with SDPF and Reception of Data  | The files shall be individually FTP'd from the DDF FSE via FTP GET command    |                                  |
| V1-ICT-<br>06-003 | 2.009        | LaRC<br>DAAC | Exit FTP connection   | Terminate FTP link with SDPF  |   |                                  |
| V1-ICT-<br>06-003 | 2.010        | LaRC<br>DAAC | Verify that the appropriate files (as indicated in DAN) containing TRMM Ephemeris Data are ingested into the ECS and that they are valid. | Upon successful ingest, the data files shall be stored and are valid.   |   | TRMM12<br>00#A<br>TRMM12<br>10#A |
| V1-ICT-<br>06-003 | 2.011        | LaRC<br>DAAC | Verify that a DDN is sent to<br>the SDPF indicating the<br>successful status of the data<br>transfer.                                     | A message or log file should indicate transfer of the DDN.  |   |                                  |
| V1-ICT-<br>06-003 | 2.012        | SDPF         | Verify the successful receipt of the DDN and the transfer of the DDA to the LaRC DAAC.  | A message or log file should indicate successful receipt of the DDN and transfer of the DDA   |   |                                  |
| V1-ICT-<br>06-003 | 2.013        | LaRC<br>DAAC | Verify the successful receipt of the DDA.   | A message or log file should indicate successful receipt of the DDA.  | This step completes<br>the transfer of the<br>TRMM Ephemeris<br>data Product. |                                  |
| V1-ICT-<br>06-003 | 2.014        | Both         | Verify the connection between the two systems has been terminated.  | No connection should exist following the end of the exchange messages.  |   |                                  |
| V1-ICT-<br>06-003 | 2.015        | LaRC<br>DAAC | Query the DAACs archive to verify the storage of the data   | Both the metadata and product should be stored in its   |   |                                  |

| Test<br>Case ID | Step<br>Type | Station | Operator action                       | Expected Result        | Comments | Allocated<br>Require<br>ments |
|-----------------|--------------|---------|---------------------------------------|------------------------|----------|-------------------------------|
|                 |              |         | product and it's associated metadata. | appropriate locations. |          |                               |

## ICT6.4 Multiple CERES Product Transfers

**Under Review** 

Not updated from 10/15 Version

SDPF will send multiple DANs (products of L0, Quicklook and TRMM Ancillary Data) in quick succession to the LaRC DAAC to initiate the transfer of the data products to the LaRC DAAC. The DAAC will verify that the products are placed in the ingest queue, and that any priorities for product type are properly assigned (a higher priority should be given to the Quicklook product due to the need of a quick distribution). SDPF (DDF) and the DAAC will monitor the transfer and verify successful completion. Upon completion of the automated transfer, the LaRC DAAC storage archive will be queried for the proper storage of the products and their associated metadata

## Requirements Satisfied:

Derived

**Test Procedures:** 

#### Test Set-up:

| Step | Station               | Action  | <b>Expected Results</b>   | Comments  |
|------|-----------------------|---|---|---|
| 1.   | SDPF                  | Verify SDPF is operational in appropriate Mode and Configuration - i.e. Capable of supporting Electronic Distribution | If it is not in proper mode, the system shall be appropriately initialized. | Exact procedures are outside<br>of scope of test, supporting<br>personnel will be responsible<br>for their execution. |
| 2.   | LaRC DAAC             | Verify LaRC DAAC is operational in a mode capable of supporting test.   | If it is not in proper mode, the system shall be appropriately initialized. | Exact procedures are outside of scope of test, supporting personnel will be responsible for their execution.          |
| 3.   | SDPF and<br>LaRC DAAC | Validate IP Address and<br>Password information   | Both systems should contain the valid information.                          | This step is needed to ensure flawless test execution.  |
| 4.   | SDPF                  | Verify connection capabilities between DDF MSE and DAAC   | Successful 'Ping' of other system   | This is the interface for transfer of control messages  |
| 5.   | LaRC DAAC             | Verify connection capabilities between DAAC and DDF FSE   | Successful 'Ping' of other system   | This is the interface for Product Transfer  |

| 6. | SDPF | Verify contents of test data | The test data shall be of | Generically, this step is to |
|----|------|------------------------------|---------------------------|------------------------------|
|    |      |                              | the appropriate           | verify the data to be        |
|    |      |                              | Instrument, size and      | transmitted during the test  |
|    |      |                              | format as required by     | execution is in fact "good". |
|    |      |                              | the test.                 | -                            |

# Test Execution:

| Step | Station   | Action   | Expected Results   | Comments   |
|------|-----------|--|--|--|
| 1.   | SDPF      | Perform necessary pre-processing in order to initiate the automated transfer of the data products.           | The SDPF will transmit the 'Authentication Request' to the LaRC DAAC.  | SDPF Operational procedures will be followed. Note also that the 'Authentication Request' will only be sent once. This is due to the fact that the automated process first checks for a connection between the two systems, if one exists, there is no need to re-authorize. |
| 2.   | LaRC DAAC | Verify receipt and validation of 'Authentication Request', verify 'Authentication Response' is sent to SDPF. | LaRC DAAC shall<br>accept and validate the<br>'Authentication<br>Request' and respond<br>with a valid<br>'Authentication<br>Response'  |  |
| 3.   | SDPF      | Verify receipt and validation of 'Authentication Response'   | The Network connection between the SDPF and LaRC DAAC shall be successfully opened.  |  |
| 4.   | SDPF      | Verify that the DANs are transferred to the LaRC DAAC.   | A message or log file should indicate transfer of the DANs.  |  |
| 5.   | LaRC DAAC | Verify successful receipt and validation of the DANs.  | A message or log file should indicate the successful receipt and validation of the DANs. The data files shall be placed in the Ingest queue, with priority, and a Short DAA shall be transferred to the SDPF for each DAN. | The datafiles from quicklook products should be placed in the ingest queue with a higher priority than the L0 or ancillary products.   |
| 6.   | SDPF      | Verify the successful receipt of the DAAs.   | A message or log file should indicate successful receipt of the DAAs.  |  |

| 7.  | LaRC DAAC | Verify that the appropriate files (as indicated in DAN) are ingested into the ECS.                                | Upon successful ingest, the data files shall be placed in a transferred to a permanent archive and appropriate Metadata should be produced. | When the files reach the top of the ingest queue, they shall be individually FTP'd from the DDF FSE via FTP GET command. |
|-----|-----------|---|---|--|
| 8.  | LaRC DAAC | Verify that a DDN is sent to the SDPF indicating the successful status of the data transfer for each of the DANs. | A message or log file should indicate transfer of the DDNs.   |  |
| 9.  | SDPF      | Verify the successful receipt of the DDNs and the transfer of the DDAs to the LaRC DAAC.                          | A message or log file should indicate successful receipt of the DDNs and transfer of the DDAs.  |  |
| 10. | LaRC DAAC | Verify the successful receipt of the DDA.   | A message or log file should indicate successful receipt of the DDA.  | This step completes the transfer of the SDPF Data Products.  |
| 11. | Both      | Verify the connection between the two systems has been terminated.  | No connection should exist following the end of the exchange messages.  | The connection between systems shall remain open until the last of the DDAs are received.                                |
| 12. | LaRC DAAC | Query the DAACs archive to verify the storage of the data products and their associated metadata.                 | Both the metadata and products should be stored in their appropriate locations.   |  |

#### **Test Termination:**

| Step | Station   | Action                             | <b>Expected Results</b> | Comments                  |
|------|-----------|------------------------------------|-------------------------|---------------------------|
| 1.   | SDPF      | Return the SDPF DDF system to      |                         | Leave things as they were |
|      |           | the state 'Operational Mode' it    |                         | found                     |
|      |           | was in prior to the test.          |                         |                           |
| 2.   | LaRC DAAC | Return the LaRC DAAC to the        |                         | Leave things as they were |
|      |           | state it was in prior to the test. |                         | found                     |

## ICT6.5 Error Handling

#### **Description:**

The purpose of this test is to ensure LaRC DAACs implementation of error handling during the automated data transfer process between the SDPF and LaRC DAAC. This testcase is broken into four sub-tests, each of which testing the LaRC DAACs error handling of a specific control message.

## Special Notes:

The SDPF maybe unable to support these testcases due the necessity of inducing error conditions. If this is the case, we will use DESIM to simulate the capabilities of the SDPF DDF EDS. (is DESIM not a part of SDPF?)

Errors can be induced either on the sending side - by manipulating messages before they are transmitted or on the receiving side - by manipulating the expected values which the control messages are to be validated against. The exact method for inducing error conditions need be resolved prior to test execution.

#### ICT6.5.1 Error Handling - Authentication Message

#### Description:

This testcase is to ensure that the LaRC DAAC is capable of detecting error conditions in 'Authentication Requests' received from the SDPF and to verify that permission to connect is rejected upon detection of such errors. The 'Test Execution' procedures will be executed for each of the following invalid authentication requests from the SDPF:

| Error-1 | Invalid Message Type  |
|---------|---|
| Error-2 | Invalid source system code                                    |
| Error-3 | Message length parameter does not match actual message length |
| Error-4 | Invalid destination system code                               |
| Error-5 | Invalid User ID   |
| Error-6 | Invalid Password  |

## **Requirements Satisfied:**

#### TRMM1080

## **Test Procedures:**

#### Test Set-up:

| Step | Station               | Action  | <b>Expected Results</b>   | Comments  |
|------|-----------------------|---|---|---|
| 1.   | SDPF and<br>LaRC DAAC | Determine the methods of inducing the necessary error conditions and generate any necessary data or database changes.                   | The necessary<br>system/data modifications<br>will be ready to support<br>the error testing | This step should be executed well in advanced of anticipated text execution date.                                     |
| 2.   | SDPF                  | Verify SDPF is operational with<br>the appropriate Mode and<br>Configuration - i.e. Capable of<br>supporting Electronic<br>Distribution | If it is not in proper mode, the system shall be appropriately initialized.                 | Exact procedures are outside<br>of scope of test, supporting<br>personnel will be responsible<br>for their execution. |
| 3.   | LaRC DAAC             | Verify LaRC DAAC is operational in a mode capable of supporting test.   | If it is not in proper mode, the system shall be appropriately initialized.                 | Exact procedures are outside of scope of test, supporting personnel will be responsible for their execution.          |
| 4.   | SDPF and<br>LaRC DAAC | Validate IP Address and<br>Password information   | Both systems should contain the valid information.  | This step is needed to ensure flawless test execution.  |
| 5.   | SDPF                  | Verify connection capabilities between DDF MSE and DAAC   | Successful 'Ping' of other system   | This is the interface for transfer of control messages  |

| 6. | LaRC DAAC | Verify connection capabilities | Successful 'Ping' of other | This is the interface for data |
|----|-----------|--------------------------------|----------------------------|--------------------------------|
|    |           | between DAAC and DDF FSE       | system                     | transfer                       |
| 7. | SDPF      | Verify contents of test data   | The test data shall be of  | Generically, this step is to   |
|    |           |                                | the appropriate            | verify the data to be          |
|    |           |                                | Instrument, size and       | transmitted during the test    |
|    |           |                                | format as required by the  | execution is in fact "good".   |
|    |           |                                | test.                      |                                |

## Test Execution:

| Step | Station   | Action                           | <b>Expected Results</b>     | Comments                        |
|------|-----------|----------------------------------|-----------------------------|---------------------------------|
| 1.   | SDPF      | Perform necessary pre-           | The SDPF will transmit      | SDPF Operational procedures     |
|      |           | processing in order to initiate  | the 'Authentication         | will be followed.               |
|      |           | the automated transfer of the    | Request' to the LaRC        |                                 |
|      |           | data products.                   | DAAC.                       |                                 |
| 2.   | LaRC DAAC | Verify receipt and validation of | For Error-1 and Error-2     | For Error-1 and Error-2 LaRC    |
|      |           | 'Authentication Request', verify | LaRC DAAC should            | DAAC will be unable to either   |
|      |           | 'Authentication Response' is     | break connection            | identify the type of message    |
|      |           | sent to SDPF.                    | immediately. For Error-3    | received or the source of the   |
|      |           |                                  | through Error-7 LaRC        | message, thus rendering itself  |
|      |           |                                  | DAAC should send SDPF       | unable to respond to the error. |
|      |           |                                  | an 'Authentication          |                                 |
|      |           |                                  | Response' with              |                                 |
|      |           |                                  | disposition set to 'Reject' |                                 |
|      |           |                                  | and immediately break       |                                 |
|      |           |                                  | the connection.             |                                 |
| 3.   | SDPF      | For Error-3 through Error-7      | The message should be       |                                 |
|      |           | verify receipt and logging of    | received with the           |                                 |
|      |           | 'Authentication Response'.       | appropriate error           |                                 |
|      |           |                                  | indicated.                  |                                 |

## Test Termination:

| Step | Station   | Action  | <b>Expected Results</b> | Comments                  |
|------|-----------|---|-------------------------|---------------------------|
| 1.   | SDPF      | Return the SDPF DDF system to . Leave things as the       |                         | Leave things as they were |
|      |           | the state 'Operational Mode' it was in prior to the test. |                         | found                     |
| 2.   | LaRC DAAC | Return the LaRC DAAC to the                               |                         | Leave things as they were |
|      |           | state it was in prior to the test.                        |                         | found                     |

# ICT6.5.2 Error Handling - Data Availability Notice

# **Description:**

This testcase is to ensure that the LaRC DAAC is capable of discovering error conditions in 'Data Availability Notices' received from the SDPF and verify LaRC DAACs ability to respond with a Data Availability Acknowledgment with disposition set to 'Reject' and the

appropriate error indicated. Recall that there are two classes of DAN errors, the first indicating that an error was discovered in the DANs header and the second indicating errors in the individual file description PVL. This test will be executed for each of the following error conditions. Remember that the type of DAA is dependent on the type of error encountered; Case-1 errors will result in Short DAAs and Case-2 errors will result in Long DAAs.

| Error-1  | Invalid DDF Control System ID |
|----------|-------------------------------|
| Error-2  | Invalid DAN sequence number   |
| Error-3  | Invalid Project ID            |
| Error-4  | Invalid Mission ID            |
| Error-5  | Invalid DDF File System ID    |
| Error-6  | Invalid file count            |
| Error-7  | Invalid data service          |
| Error-8  | EDU label error               |
| Error-9  | DAN label error               |
| Error-10 | Invalid DAN length            |
| Error-11 | Invalid aggregate length      |
|          |                               |

Database failures

Duplicate DAN sequence number

Short DAA reports

Case-1

## Case-2 Long DAA Reports

Error-12

Error-13

Error-25

| Error-14 | Invalid Data Version           |
|----------|--------------------------------|
| Error-11 | Invalid data type              |
| Error-16 | Invalid distribution criteria  |
| Error-12 | Invalid descriptor             |
| Error-13 | Invalid directory              |
| Error-19 | Invalid time stamp format      |
| Error-20 | Invalid generation time format |
| Error-14 | Invalid file size field        |
| Error-15 | Invalid short file ID          |
| Error-16 | Invalid time/data format       |
| Error-24 | Invalid FILE_ID                |
|          |                                |

11/16/96 ICT6-18

Duplicate file group ID

Proper values for these parameters are specified in Tables 4-3 and 4-6 of the Sensor Data Processing Facility (SDPF) Consumer Products and Interface Specification Document (510-203.102);

Requirements Satisfied:

TRMM1080

<u>Test Procedures:</u>

# Test Set-up:

| Step | Station   | Action                           | <b>Expected Results</b>    | Comments                       |
|------|-----------|----------------------------------|----------------------------|--------------------------------|
| 1.   | SDPF and  | Determine the methods of         | The necessary              | This step should be executed   |
|      | LaRC DAAC | inducing the necessary error     | system/data modifications  | well in advanced of            |
|      |           | conditions and generate any      | will be ready to support   | anticipated text execution     |
|      |           | necessary data or database       | the error testing          | date.                          |
|      |           | changes.                         |                            |                                |
| 2.   | SDPF      | Verify SDPF is operational with  | If it is not in proper     | Exact procedures are outside   |
|      |           | the appropriate Mode and         | mode, the system shall be  | of scope of test, supporting   |
|      |           | Configuration - i.e. Capable of  | appropriately initialized. | personnel will be responsible  |
|      |           | supporting Electronic            |                            | for their execution.           |
|      |           | Distribution                     |                            |                                |
| 3.   | LaRC DAAC | Verify LaRC DAAC is              | If it is not in proper     | Exact procedures are outside   |
|      |           | operational in a mode capable of | mode, the system shall be  | of scope of test, supporting   |
|      |           | supporting test.                 | appropriately initialized. | personnel will be responsible  |
|      |           |                                  |                            | for their execution.           |
| 4.   | SDPF and  | Validate IP Address and          | Both systems should        | This step is needed to ensure  |
|      | LaRC DAAC | Password information             | contain the valid          | flawless test execution.       |
|      |           |                                  | information.               |                                |
| 5.   | SDPF      | Verify connection capabilities   | Successful 'Ping' of other | This is the interface for      |
|      |           | between DDF MSE and DAAC         | system                     | transfer of control messages   |
| 6.   | LaRC DAAC | Verify connection capabilities   | Successful 'Ping' of other | This is the interface for data |
|      |           | between DAAC and DDF FSE         | system                     | transfer                       |
| 7.   | SDPF      | Verify contents of test data     | The test data shall be of  | Generically, this step is to   |
|      |           |                                  | the appropriate            | verify the data to be          |
|      |           |                                  | Instrument, size and       | transmitted during the test    |
|      |           |                                  | format as required by the  | execution is in fact "good".   |
|      |           |                                  | test.                      |                                |

#### Test Execution:

| Step | Station | Action                          | Expected Results       | Comments                    |
|------|---------|---------------------------------|------------------------|-----------------------------|
| 1.   | SDPF    | Perform necessary pre-          | The SDPF will transmit | SDPF Operational procedures |
|      |         | processing in order to initiate | the 'Authentication    | will be followed.           |
|      |         | the automated transfer of the   | Request' to the LaRC   |                             |
|      |         | data products.                  | DAAC.                  |                             |

| 2. | LaRC DAAC | Verify receipt and validation of 'Authentication Request', verify 'Authentication Response' is sent to SDPF. | LaRC DAAC shall accept<br>and validate the<br>'Authentication Request'<br>and respond with a valid<br>'Authentication<br>Response'   |  |
|----|-----------|--|--|--|
| 3. | SDPF      | Verify receipt and validation of<br>'Authentication Response'  | The Network connection between the SDPF and LARC DAAC shall be successfully opened.  |  |
| 4. | SDPF      | Verify that the erred DAN is transferred to the LaRC DAAC.   | A message or log file should indicate transfer of the DAN.   |  |
| 5. | LaRC DAAC | Verify successful receipt and validation of the DAN.   | For Case-1 DANs, LaRC DAAC should respond with a short DAA reporting the error discovered in the DAN. For Case-2 DANs, LaRC DAAC should respond with a Long DAA indicating the erred file group and the error condition. | In either case, LaRC should<br>not ingest any files from an<br>erred DAN |
| 6. | SDPF      | Verify the successful receipt of the DAA.  | Status of the DAA should<br>be provided to the system<br>operator in order to<br>perform necessary<br>manual error correction.   |  |

#### Test Termination:

| Step | Station   | Action                             | Expected Results | Comments                  |
|------|-----------|------------------------------------|------------------|---------------------------|
| 1.   | SDPF      | Return the SDPF DDF system to      |                  | Leave things as they were |
|      |           | the state, 'Operational Mode', it  |                  | found                     |
|      |           | was in prior to the test.          |                  |                           |
| 2.   | LaRC DAAC | Return the LaRC DAAC to the        |                  | Leave things as they were |
|      |           | state it was in prior to the test. |                  | found                     |

## ICT6.5.3 Error Handling - FTP Get

#### **Description:**

This testcase is designed to ensure the capabilities of LaRC DAAC to handle errors encountered during the FTP of files from the SDPF DDF Files Servers. The LaRC DAAC should be able to either recover from the error condition (through the use of multiple retries) or abort the transfer attempts and inform the system operator and SDPF of the error condition. The SDPF will be informed through the use of Data Delivery Notices (DDN). A short DDN will be used to indicate system level errors (e.g. unable to logon to specific SDPF File Server) or errors common to all files in the product and Long DAAs

will be used to indicate errors at the individual file level (e.g. File Not Found). This testcase will be executed for each of the following FTP error conditions, Case 1 errors will result in Short DDNs and Case-2 errors will result in Long DDNs.

| Case-1 | Short DDN reports |
|--------|-------------------|
|        | <b>.</b>          |

| Error-1       | Network Failure                                |  |
|---------------|--|--|
| Error-2       | Unable to Establish FTP Connection             |  |
| Error-3       | Host Denied Access                             |  |
| Error-4       | File not found                                 |  |
| Error-5       | FTP failure - Too many errors in file transfer |  |
| Error-6       | Post-transfer double-check failure             |  |
| Error-7       | FTP command failure                            |  |
| Case-2 Long I | DDN reports                                    |  |
| Error-8       | Network Failure                                |  |
| Error-9       | Unable to Establish FTP Connection             |  |
| Error-10      | Host Denied Access                             |  |
| Error-11      | File not found                                 |  |
|               |  |  |

Error-12 FTP failure - Too many errors in file transfer

Error-13 Post-transfer double-check failure

Error-14 FTP command failure

# Requirements Satisfied:

#### TRMM1080

## Test Procedures:

#### Test Set-up:

| Step | Station   | Action                          | <b>Expected Results</b>    | Comments                      |
|------|-----------|---------------------------------|----------------------------|-------------------------------|
| 1.   | SDPF and  | Determine the methods of        | The necessary              | This step should be executed  |
|      | LaRC DAAC | inducing the necessary error    | system/data modifications  | well in advanced of           |
|      |           | conditions and generate any     | will be ready to support   | anticipated text execution    |
|      |           | necessary data or database      | the error testing          | date.                         |
|      |           | changes.                        |                            |                               |
| 2.   | SDPF      | Verify SDPF is operational with | If it is not in proper     | Exact procedures are outside  |
|      |           | the appropriate Mode and        | mode, the system shall be  | of scope of test, supporting  |
|      |           | Configuration - i.e. Capable of | appropriately initialized. | personnel will be responsible |
|      |           | supporting Electronic           |                            | for their execution.          |
|      |           | Distribution                    |                            |                               |

| 3. | LaRC DAAC | Verify LaRC DAAC is              | If it is not in proper     | Exact procedures are outside   |
|----|-----------|----------------------------------|----------------------------|--------------------------------|
|    |           | operational in a mode capable of | mode, the system shall be  | of scope of test, supporting   |
|    |           | supporting test.                 | appropriately initialized. | personnel will be responsible  |
|    |           |                                  |                            | for their execution.           |
| 4. | SDPF and  | Validate IP Address and          | Both systems should        | This step is needed to ensure  |
|    | LaRC DAAC | Password information             | contain the valid          | flawless test execution.       |
|    |           |                                  | information.               |                                |
| 5. | SDPF      | Verify connection capabilities   | Successful 'Ping' of other | This is the interface for      |
|    |           | between DDF MSE and DAAC         | system                     | transfer of control messages   |
| 6. | LaRC DAAC | Verify connection capabilities   | Successful 'Ping' of other | This is the interface for data |
|    |           | between DAAC and DDF FSE         | system                     | transfer                       |
| 7. | SDPF      | Verify contents of test data     | The test data shall be of  | Generically, this step is to   |
|    |           |                                  | the appropriate            | verify the data to be          |
|    |           |                                  | Instrument, size and       | transmitted during the test    |
|    |           |                                  | format as required by the  | execution is in fact "good".   |
|    |           |                                  | test.                      |                                |

# Test Execution:

| Step | Station   | Action                           | <b>Expected Results</b>     | Comments                       |
|------|-----------|----------------------------------|-----------------------------|--------------------------------|
| 1.   | SDPF      | Perform necessary pre-           | The SDPF will transmit      | SDPF Operational procedures    |
|      |           | processing in order to initiate  | the 'Authentication         | will be followed and the       |
|      |           | the automated transfer of the    | Request' to the LaRC        | distribution of the product to |
|      |           | TRMM Ancillary Data Product.     | DAAC.                       | the LaRC DAAC will begin.      |
| 2.   | LaRC DAAC | Verify receipt and validation of | LaRC DAAC shall accept      |                                |
|      |           | 'Authentication Request', verify | and validate the            |                                |
|      |           | 'Authentication Response' is     | 'Authentication Request'    |                                |
|      |           | sent to SDPF.                    | and respond with a valid    |                                |
|      |           |                                  | 'Authentication             |                                |
|      |           |                                  | Response'                   |                                |
| 3.   | SDPF      | Verify receipt and validation of | The Network connection      |                                |
|      |           | 'Authentication Response'        | between the SDPF and        |                                |
|      |           |                                  | LARC DAAC shall be          |                                |
|      |           |                                  | successfully opened.        |                                |
| 4.   | SDPF      | Verify DAN is transferred to the | A message or log file       |                                |
|      |           | LaRC DAAC.                       | should indicate transfer of |                                |
|      |           |                                  | the DAN.                    |                                |
| 5.   | LaRC DAAC | Verify successful receipt and    | A message or log file       |                                |
|      |           | validation of the DAN.           | should indicate the         |                                |
|      |           |                                  | successful receipt and      |                                |
|      |           |                                  | validation of the DAN.      |                                |
|      |           |                                  | The data files shall be     |                                |
|      |           |                                  | placed in the Ingest queue  |                                |
|      |           |                                  | and a Short DAA shall be    |                                |
|      |           |                                  | transferred to the SDPF.    |                                |
| 6.   | SDPF      | Verify the successful receipt of | A message or log file       |                                |
|      |           | the DAA.                         | should indicate successful  |                                |
|      |           |                                  | receipt of the DAA          |                                |
|      |           |                                  |                             |                                |

Only Execute the Procedures for the Specific Error Case. ERROR-1

| 7.     |         |  |  |  |  |
|--------|---------|--|--|--|--|
| 8.     |         |  |  |  |  |
| 9.     |         |  |  |  |  |
| ERROR- | -2      |  |  |  |  |
| 7.     |         |  |  |  |  |
| 8.     |         |  |  |  |  |
| 9.     |         |  |  |  |  |
| ERROR- | -3      |  |  |  |  |
| 7.     |         |  |  |  |  |
| 8.     |         |  |  |  |  |
| 9.     |         |  |  |  |  |
| ERROR- | -4      |  |  |  |  |
| 7.     |         |  |  |  |  |
| 8.     |         |  |  |  |  |
| 9.     |         |  |  |  |  |
| ERROR- | -5      |  |  |  |  |
| 7.     |         |  |  |  |  |
| 8.     |         |  |  |  |  |
| 9.     |         |  |  |  |  |
| ERROR- | -6      |  |  |  |  |
| 7.     |         |  |  |  |  |
| 8.     |         |  |  |  |  |
| 9.     |         |  |  |  |  |
| ERROR- | ERROR-7 |  |  |  |  |
| 7.     |         |  |  |  |  |
| 8.     |         |  |  |  |  |
| 9.     |         |  |  |  |  |
|        |         |  |  |  |  |

#### **Test Termination:**

| Step | Station   | Action                             | <b>Expected Results</b> | Comments                  |
|------|-----------|------------------------------------|-------------------------|---------------------------|
| 1.   | SDPF      | Return the SDPF DDF system to      |                         | Leave things as they were |
|      |           | the state 'Operational Mode' it    |                         | found                     |
|      |           | was in prior to the test.          |                         |                           |
| 2.   | LaRC DAAC | Return the LaRC DAAC to the        |                         | Leave things as they were |
|      |           | state it was in prior to the test. |                         | found                     |

#### ICT6.5.4 Error Handling - Data Delivery Acknowledgment

#### Description:

Upon the completion of data receipt from the SDPF, the LaRC DAAC shall transfer a DDN indicating the success of the transfer. Upon receipt of the DDN, the SDPF shall want to reply with a DDA. This DDA will be altered prior to transferring it to the LaRC DAAC. The LaRC DAAC shall receive the erred DDA, and respond to it in an appropriate manner -TBD. This testcase will be executed for each of the following DDA error types:

Disposition-1 No DDA Transmitted

Disposition-2 Error Recovery Being Invoked

# **Requirements Satisfied:**

# TRMM1080

# Test Procedures:

# Test Set-up:

| Step | Station   | Action                             | <b>Expected Results</b>                              | Comments   |
|------|-----------|------------------------------------|--|--|
| 1.   | SDPF and  | Determine the methods of           | The necessary  | This step should be executed                               |
|      | LaRC DAAC | inducing the necessary error       | system/data modifications                            | well in advanced of  |
|      |           | conditions and generate any        | will be ready to support                             | anticipated text execution                                 |
|      |           | necessary data or database         | the error testing                                    | date.  |
|      | CDDE      | changes.                           | TC:  | P . 1  |
| 2.   | SDPF      | Verify SDPF is operational with    | If it is not in proper                               | Exact procedures are outside                               |
|      |           | the appropriate Mode and           | mode, the system shall be                            | of scope of test, supporting                               |
|      |           | Configuration - i.e. Capable of    | appropriately initialized.                           | personnel will be responsible                              |
|      |           | supporting Electronic Distribution |  | for their execution.                                       |
| 3.   | LaRC DAAC |                                    | TC:4:  | E  |
| 3.   | Lake DAAC | Verify LaRC DAAC is                | If it is not in proper                               | Exact procedures are outside                               |
|      |           | operational in a mode capable of   | mode, the system shall be appropriately initialized. | of scope of test, supporting personnel will be responsible |
|      |           | supporting test.                   | appropriately illitialized.                          | for their execution.                                       |
| 4.   | SDPF and  | Validate IP Address and            | Both systems should                                  | This step is needed to ensure                              |
| 4.   | LaRC DAAC | Password information               | contain the valid                                    | flawless test execution.                                   |
|      | Lake DAAC | r assword information              | information.   | mawiess test execution.                                    |
| 5.   | SDPF      | Verify connection capabilities     | Successful 'Ping' of other                           | This is the interface for                                  |
| J.   | SDIT      | between DDF MSE and DAAC           | system   | transfer of control messages                               |
| 6.   | LaRC DAAC | Verify connection capabilities     | Successful 'Ping' of other                           | This is the interface for data                             |
| 0.   | Lake DAAC | between DAAC and DDF FSE           | system   | transfer   |
| 7.   | SDPF      | Verify contents of test data       | The test data shall be of                            | Generically, this step is to                               |
| ''   |           | verify contents of test data       | the appropriate                                      | verify the data to be                                      |
|      |           |                                    | Instrument, size and                                 | transmitted during the test                                |
|      |           |                                    | format as required by the                            | execution is in fact "good".                               |
|      |           |                                    | test.  | l marting in the good .                                    |

# Test Execution:

| Step | Station   | Action                           | <b>Expected Results</b>  | Comments                       |
|------|-----------|----------------------------------|--------------------------|--------------------------------|
| 1.   | SDPF      | Perform necessary pre-           | The SDPF will transmit   | SDPF Operational procedures    |
|      |           | processing in order to initiate  | the 'Authentication      | will be followed and the       |
|      |           | the automated transfer of the    | Request' to the LaRC     | distribution of the product to |
|      |           | TRMM Ancillary Data Product.     | DAAC.                    | the LaRC DAAC will begin.      |
| 2.   | LaRC DAAC | Verify receipt and validation of | LaRC DAAC shall accept   |                                |
|      |           | 'Authentication Request', verify | and validate the         |                                |
|      |           | 'Authentication Response' is     | 'Authentication Request' |                                |
|      |           | sent to SDPF.                    | and respond with a valid |                                |
|      |           |                                  | 'Authentication          |                                |
|      |           |                                  | Response'                |                                |

|         | 1          |   | I  |   |
|---------|------------|---|--|---|
| 3.      | SDPF       | Verify receipt and validation of<br>'Authentication Response'   | The Network connection between the SDPF and LARC DAAC shall be successfully opened.  |   |
| 4.      | SDPF       | Verify DAN is transferred to the LaRC DAAC.   | A message or log file should indicate transfer of the DAN.   |   |
| 5.      | LaRC DAAC  | Verify successful receipt and validation of the DAN.  | A message or log file should indicate the successful receipt and validation of the DAN. The data files shall be placed in the Ingest queue and a Short DAA shall be transferred to the SDPF. |   |
| 6.      | SDPF       | Verify the successful receipt of the DAA.   | A message or log file<br>should indicate successful<br>receipt of the DAA  |   |
| 7.      | LaRC DAAC  | Verify that the appropriate files (as indicated in DAN) are ingested into the ECS.  | Upon successful ingest,<br>the data files shall be<br>placed in a transferred to<br>a permanent archive and<br>appropriate Metadata<br>should be produced.                                   | When the files reach the top of the ingest queue, they shall be individually FTP'd from the DDF FSE via FTP GET command.  |
| 8.      | LaRC DAAC  | Verify that a DDN is sent to the SDPF indicating the successful status of the data transfer.  | A message or log file should indicate transfer of the DDN.   |   |
| For Dis | position-1 |   |  |   |
| 9.      | SDPF       | Verify the successful receipt of the DDN, but do not transmit a DDA to the LaRC DAAC.   | A message or log file should indicate successful receipt of the DDN.   |   |
| 10.     | LaRC DAAC  | Verify that LaRC DAAC retransmits the DDN to the SDPF.  | LaRC DAAC re-transmits the DDN to the SDPF.  | There should be an operator tunable parameter indicating how long LaRC DAAC will wait for a DDA. This will be located either in a database or a flat file.                  |
| 11.     | Both       | Repeat steps 9 - 10 until the number of retry attempts for sending DDA's is met.  |  | There should be an operator tunable parameter indicating how long reties should be attempted for sending the DDA. This will be located either in a database or a flat file. |
| 12.     | LaRC       | Upon the number of retries reaching the retry parameter, an error condition shall be set indicated the error to the LaRC system operator. |  |   |

For Disposition-2

|     | 1         | 1                                |                            |  |
|-----|-----------|----------------------------------|----------------------------|--|
| 9.  | SDPF      | Verify the successful receipt of | A message or log file      |  |
|     |           | the DDN and the transfer of the  | should indicate successful |  |
|     |           | appropriate erred DDA to the     | receipt of the DDN and     |  |
|     |           | LaRC DAAC.                       | transfer of the DDA        |  |
| 10. | LaRC DAAC | Verify the successful receipt of | A message or log file      |  |
|     |           | the DDA.                         | should indicate successful |  |
|     |           |                                  | receipt of the DDA. The    |  |
|     |           |                                  | error condition shall be   |  |
|     |           |                                  | discovered and the         |  |
|     |           |                                  | appropriate action should  |  |
|     |           |                                  | be taken. System           |  |
|     |           |                                  | operator should be         |  |
|     |           |                                  | notified of the error      |  |
|     |           |                                  | condition.                 |  |

# Test Termination:

| Step | Station   | Action                             | <b>Expected Results</b> | Comments                  |
|------|-----------|------------------------------------|-------------------------|---------------------------|
| 1.   | SDPF      | Return the SDPF DDF system to      |                         | Leave things as they were |
|      |           | the state 'Operational Mode' it    |                         | found                     |
|      |           | was in prior to the test.          |                         |                           |
| 2.   | LaRC DAAC | Return the LaRC DAAC to the        |                         | Leave things as they were |
|      |           | state it was in prior to the test. |                         | found                     |